TRAIL LAKE

SPECIFICATIONS

Fiber System: 100%PP

Modular Size:(in cms) 50 X 50 / 25 X 100

Modular Size:(in inches) 19.7 X 19.7 / 9.84 X 39.37

Backing System: PVC

Construction: High- Low Loop Machine Tufted

Gauge: 8+4

Pile Height: 2.5-4.0mm (\pm 5%)

Pile Weight: 450g/m (+5%)

Carton Weight:50.99lb

Floor Vek

CARTON CONFIGURATION


Pcs/Carton: 24 pcs Sqft/Carton: 64.58 Sqyd/Carton: 7.18 Packaging: Carton

Installation: Following the Backing Direction.

WARRANTIES

Lifetime Commercial Wear Lifetime Backing Performance

INSTALLATION METHODS



1. Quarter-turn

2. Monolithic

3. Brick

4. Ashlar

